SHUBHAM™ TANKS AND LINERS

**SHUBHAM TANKS AND LINERS PVT. LTD.**

128,Lodha Supremus-II, North Wing,
Road No.22, Wagle Industrial Estate,
Thane, Pin - 400604, State : Maharashtra, India
Phone No : 022-49748989, Website : www.shubhamtanks.com
GST No : 27ABECS2311L1ZD

# QUOTATION

**Customer's Details:** **Customer Code:** A121

**Aventura Components (FZE)**

PO Box 513286, SAIF Zone,
-513286, United Arab Emirates
Ph. No: +971 50 825 8264
E-Mail: pawan.verma@aventura.co.in

**Quotation No :** 26-27/SQ/1898
**Quotation Date :** 19/10/2026
**Revision No :** 0
**Quotation Date :** 19/10/2026
**Enq. Ref :** By Email

**Project** : SQ/26-27/1898 Kunal Bansode M NO : +91 8655947916

**Kind Attn. : Mr. Pawan Verma**

Contact No: +971 50 825 8264, Email: pawan.verma@aventura.co.in

Dear Sir,
Thank you for the subject enquiry. Basis the technical parameters of the liquid shared by you and our subsequent discussion, we are pleased to share the technical details of our tanks followed by the commercial offer for your perusal.

| No. | Item Details & Specification | UOM | Quantity | Rate (USD) | Amount (USD) |
|---|---|---|---|---|---|
| 1 | **Supply of Secure Store Water Storage Tank (SST)** | NOS | | | |
| | HSN / SAC Code: 73090090 | | | | |
| | **SST 475-60**; Dia : 16.04m ; Ht : 6.0m ; Gross Cap : 1219KL | | 1.00 | 45,500.00 | 45,500.00 |
| | **Remark: Equalization Tank (Closed Type Roof)** | | | | |
| | **SST 85-48**; Dia : 6.88m ; Ht : 4.8m ; Gross Cap : 180KL | | 3.00 | 13,500.00 | 40,500.00 |
| | **Remark: Anoxic Tanks (Open Roof)** | | | | |
| | **SST 310-60**; DIA: 12.99M, HT: 6.03M, GROSS CAP: 800KL | | 3.00 | 29,750.00 | 89,250.00 |
| | **Remark: Aeration Tanks (Open Roof)** | | | | |
| | **SST 155-48**; Dia : 9.17m ; Ht : 4.85m ; Gross Cap : 320KL | | 3.00 | 17,500.00 | 52,500.00 |
| | **Remark: Secondary Clarifier Tank (Open Roof)** | | | | |
| | **SST 70-48**; Dia : 6.11 ; Ht : 4.85m ; Gross Cap : 142KL | | 1.00 | 12,000.00 | 12,000.00 |
| | **Remark: Chlorine Contact Tanks (Open Roof)** | | | | |
| | **SST 105-48**; Dia : 7.64 Ht : 4.8 Gross Cap : 222KL | | 1.00 | 16,000.00 | 16,000.00 |
| | **Remark: Sludge Holding Tanks (Closed Type Roof)** | | | | |
| | **SST 1720-84**; Dia : 30.56m ; Ht : 8.41m ; Gross Cap : 6162KL | | 2.00 | 173,500.00 | 347,000.00 |
| | **Remark: TSE Tanks (Closed Type Roof)** | | | | |
| | **SST 70-36;** Dia : 6.11 ; Ht : 3.66m ; Gross Cap : 105KL | | 3.00 | 9,500.00 | 28,500.00 |
| | **Remark: Internal Recirculation Tanks (Open Roof)** | | | | |
| | HDG FLANGED OUTLET 600MM (RF PAD &E TABLE) HDG SIDE | | 17.00 | | |
| | HDG CAGE LADDER 6.0 | | 4.00 | | |
| | HDG Cage ladder 4.8 | | 8.00 | | |
| | HDG Cage ladder 8.4 | | 2.00 | | |
| | HDG Cage ladder 3.6 | | 3.00 | | |
| | HDG GOOSE NECK AIRVENT 100MM (E TABLE) ASSEMBLY | | 17.00 | | |

**Remark:** **Basic Value:** 631,250.00

**USD: SIX HUNDRED THIRTY-ONE THOUSAND TWO HUNDRED FIFTY ONLY** **Total Value (USD):** **631,250.00**

SHUBHAM™
TANKS AND LINERS

Kingspan RHINO

**SHUBHAM TANKS AND LINERS PVT. LTD.**

128,Lodha Supremus-II, North Wing,
Road No.22, Wagle Industrial Estate,
Thane, Pin - 400604, State : Maharashtra, India
Phone No : 022-49748989, Website : www.shubhamtanks.com
GST No : 27ABECS2311L1ZD

FM APPROVED

ANSI / NSF 61 Certified INFINITY LINER

# QUOTATION

**Project** : SQ/26-27/1898 Kunal Bansode M NO : +91 8655947916

Scope of Work and Tank Design.
"SECURESTORE Tanks - Bolted steel storage tank structures are engineered with a predicted minimum 30+ years design life.
The design assumes a top liquid level no higher than the operational freeboard, liquor contents at ambient operating temperature with specific gravity as detailed.
Design Standards
SECURESTORE Tank technology is a unique solution which combines the advantages of both material - the strength and flexibility of the steel and high corrosion resistance of the innovative SECURECOAT micro coating technology. The materials, design, fabrication and erection of the bolt together tank shall conform to the AWWA Standard for ""Factory-Coated Bolted Steel Tanks for Water Storage"" - ANSI/AWWA D103-2009."
The Tank shall comprise of:
1. All SECURESTORE ™ bolted panel tanks are with SECURECOAT micro coating technology which
penetrates in the surface and acts in Microstructure of material giving it un-parallel
corrosion resistance
Self-locking nuts & bolts 8.8 Grade, washers with PP cap for panel assembly
Angle iron, Material: -IS 2062
SECURESTORE tanks panels of minimum 3mm thickness.
Common HDG internal ladder.
ladder - -IS 2062.
Waterproof sealant, Vertical cage ladder.
HDG SIDE MANWAY 600mm.
Powder Access hatch on Roof 600mm x 600mm.
Corrugated Hard Dome Roof with Galvalume Sheets.
HDG GOOSE NECK AIRVENT 100MM.
Color – Blue (RAL 5004)
MOC of tank sheet: Steel panels coated with proprietary Securecoat™solution.
Coating thickness: Inner- 180 -200 µ / Outer 85-95 µ.
Float and Board Level Indicator.
Nozzle Extra

**IMPORTANT NOTES :**

1. Provision for 15 Amp single phase electricity at site and minimum 25% of tank capacity of water for hydraulic testing of the tank immediately post installation
2. Nozzle orientation and elevation details to be provided minimum 3 weeks before the dispatch of tanks from the factor.
3. Once material is delivered to the customer site, responsibility for safe custody and appropriate storage (as above) of the material lies with the customer. In case of any damage or pilferage of material at customer site, STLPL will not be held responsible.
4. Any down time due to site restrictions/site not being ready or industrial action will be charged at the rate of USD 10 per hour per person, to a maximum of 8 hours per day.
5. If tanks cannot be tested within 24 hours of installation a detention fee of USD 100/- per day will be charged.
6. All fitting and associated pipe work to be manufactured from HDG steel. Flanges to be BS10 Table E or ANSI as per customer prior confirmation, and terminate 200mm from the tank wall.
7. Installers must be permitted to work up to one meter above tank height, utilizing appropriate safety equipment and arrangement of scaffolding/staging and two folding ladders up both up to the tank height and one hydra crane to be made available at site. Depending on tank capacities, additional equipment may be required.
8. Unloading of material and safe storage of at site within 10 meters of installation site. If a tank is not installed immediately, all material should be kept in the enclosed space away from the water and water logging.
9. 5-6 semi-skilled labours per tank during the installation along with PPE
10. All permissions related to safety & procedural requirements at the installation site must be provided immediately to the installation team on the day of installation
11. As per STLPL invoicing norms, tank value, installation, freight and package charges will need to be mentioned separately. Hence in case the customer is issuing a single PO, they have to mention all these separately in the PO itself

**Terms and Conditions :-**

| | |
|---|---|
| **Price** | : Above price is in USD **Ex Works** at our factory at Bhiwandi, India. |
| **Freight charges** | : Extra at actual and shall be confirmed at the time of dispatch. |

SHUBHAM™ TANKS AND LINERS

**SHUBHAM TANKS AND LINERS PVT. LTD.**

128,Lodha Supremus-II, North Wing,
Road No.22, Wagle Industrial Estate,
Thane, Pin - 400604, State : Maharashtra, India
Phone No : 022-49748989, Website : www.shubhamtanks.com
GST No : 27ABECS2311L1ZD

# QUOTATION

**Project** : SQ/26-27/1898 Kunal Bansode M NO : +91 8655947916

| | |
|---|---|
| **Packing charges** | : Standard packing charges at our factory will be **3% extra** on the quoted price. Additional charges are applicable for heat treated wooden packing which can be confirmed, if required. |
| **Installation guidance/supervision** | : Supervision of installation and commissioning charges for **one-person applicable extra USD $250 per day** to be paid before mobilization of installer from India. To & fro air fare expenses, business visa and cost of excess baggage for one supervisor per tank from Mumbai, lodging & boarding arrangements and local incidental & conveyance costs to be borne by client. |
| **Dispatch period** | : **Goods will be ready for dispatch between 14-16 weeks from the date of receipt approved drawings and manufacturing clearance and completion of Commercial formalities and documentation.** Exact dispatch timeline will be shared at the time of final negotiation, depending on the manufacturing schedule at that time. No change in the tank model will be accepted once the stamped OA is received from the customer. No change in nozzle orientation / elevation will be accepted once the cut outs have been done. |
| **Payment terms** | : **50% Advance along with LPO, Balance 50% payable when the material is ready at our factory for dispatch.** Supervision charges to be paid against PI before mobilization of the supervisor from India. |
| **Offer validity** | : **30 days from the date of this proposal,** then after subject to our confirmation in writing. |
| **Warranty** | : **Standard Conditional pro-rata STLPL Warranty of one year. Warranty manual will be issued once all the due payments are received.** Note: Once the tank is tested for leakage and certified, any leakage due to secondary activities at a later stage-like connection of pipe and valves to the nozzles will not be covered under warranty. Rectification of the same will be on paid basis and only after all due payments have been received. |
| **Force Majeure** | : Force majeure clause covering all Acts of God & unforeseen circumstance shall apply, and is detailed below: Force majeure means any unforeseen event or circumstance that is beyond the reasonable control of either party, which event cannot by exercise of reasonable diligence be prevented or caused to be prevented, and which adversely affects such party's performance of its duties and obligations or enjoyment of its rights under this proposal. Neither party hereto shall be held responsible for any delay or failure to perform any or all of the obligations imposed upon such party caused by force majeure.<br>i. In such a case, the time for performance of such obligations and the obligations of the other party to the extent that they are directly or indirectly affected by such occurrence will be extended by a period equal to that time. Notification of a circumstance of force majeure shall be given by email addressed to the other party within 7 working days of its occurrence. This email shall be confirmed by a letter dispatched within one week, along with a certificate of the relevant Chamber of Commerce or any other acceptable documentary evidence, confirming the existence of the circumstances of the force majeure.<br>ii. Only the following shall be considered as force majeure if they intervene before contractual delivery date and impede performance. Acts of God, wars, revolutions, major fire, unprecedented floods, epidemics or pandemics, quarantine restriction, government authority-imposed lock-downs and freight embargoes and official strikes (only those which exceed 10 continuous days), also extended to breakdown of critical machineries, non-availability of key raw materials, lockouts at buyer's or supplier's works or at major approved sub-contractors, under initiation of govt. regulations and laws.<br>Unless otherwise directed mutually by both parties in writing, both shall continue to perform its obligations under the Contract as far as practical, and shall seek all reasonable alternative means for performance not prevented by the force majeure event. In the event the affected Party is prevented from fulfilling its obligation under any proposed agreement owing to the force majeure condition continuing for more than 30 days, both parties shall consult each other regarding the future course of action. |

We hope the above offer is in line with your expectations and requirement. If you require any further techno-commercial clarification or information in the matter, please do not hesitate to contact us.